




Scan Me

View Project Portal

- Measuring Tools
- Interactive 3D Model
- Live Documents Online
- 3D Images
- Videos




EXISTING EASTERN ELEVATION



EXISTING CONDITIONS

PROPOSED SCHEME



PROPOSED EASTERN ELEVATION

NB21 | New Additional Side Windows

Careful consideration has been given to the new windows proposed on the eastern side elevation to ensure openings remain subservient and sympathetic to the host dwelling. The newly introduced windows have been deliberately designed as modest, proportionately small openings that are highly appropriate for a secondary side elevation. To maintain a cohesive visual appearance across the property, these windows have been chosen to replicate the traditional cottage bar design already present on the existing elevation. These proportionate additions are strictly functional, providing essential natural light and ventilation to the newly formed ground-floor WC and the new first-floor store room, while respecting the overall architectural character of the building and mitigating any potential impact on neighbouring privacy amenity.

NB02 | Roof Replacement

To secure the necessary internal head height and usable floor area for the loft conversion, the proposal features a new crown roof. The current roof structure utilises restrictive fink-style trusses, meaning a complete roof replacement is fundamentally required. A traditional apex roof was discounted as it would raise the ridge to an unacceptable height. As evidenced by the drone imagery in the Design and Access Statement, the neighbouring property at No. 9 occupies an elevated topographical position with a significantly steeper, taller roof structure, establishing a clear precedent for a higher permissible ridge line on Ashness Close. Despite this precedent, the applicant consciously opted to cap the proposed ridge height by flattening the apex into a crown design. While a more financially intensive structural solution, this approach successfully mimics a traditional pitched roof from the principal front and rear elevations, remaining faithful to the original roof pitch and rigorously protecting the established character of the street scene.

The contractor is responsible for all technical roof design and coordinating the scheme with an attic truss manufacturer (e.g., Trusstec or similar). All insulation, vapour control, and structural elements must be designed and specified in full compliance with current Building Regulations.

General Note | Planning Purpose Only

This document has been prepared explicitly for the purpose of a Planning Application. To ensure clarity for the Planning Officers assessment, the document pack is intentionally lightweight and omits detailed technical specifications, including structural arrangements, wall compositions, and floor / roof build-ups. Consequently, these documents are strictly not fit for construction purposes or Building Regulations approval. Comprehensive technical design and structural engineering plans must be commissioned and approved at a subsequent stage prior to the commencement of any works.