




PE01| North Elevation



Printed Scale Factor | 1mm : 50mm

Scale Valid When Printed At : ISO 216 A1



Global Height Benchmark

Datum GCP | Ground Floor Finished Floor Level

All height measurements on this drawing are taken from the existing ground floor finished floor level, which serves as the universal site datum benchmark unless otherwise specified. Heights are set globally based on the primary ground control point established during the survey. If exact coordinates of this ground control point are required, please contact Noble Architecture.

RP10 | Porch Roof Specification

- RF10.01 | MATERIALS & PRODUCT DETAILS**
 - Roof Type - Traditional cut pitched roof, cold roof construction; Insulated at ceiling level, ventilated roof void.
 - Pitch - 35° Roof Pitch. - Hip & Gable Ends
 - Roof Tile - Marley Edgemere interlocking concrete tile, grey finish.
 - Battens - 25 x 38 mm tanalised treated softwood roofing battens to BS 5534.
 - Underlay - BS EN 13859-1 LR (Low Resistance) breathable membrane with eaves carrier tray.
 - Rafters - 150mm x 50mm C16 timber at 400 mm centres.
 - Wall Plate - 100 x 75 mm pressure-treated timber (UC3).
 - Ceiling - 12.5 mm plasterboard with 3 mm skim coat finish.
 - Insulation - Mineral wool; 300mm Total Thickness; Required product performance - Lambda Val. Value 0.037 W/mK.
 - VCL - 500 g (125 micron) polythene vapour control layer.
 - Flashings - Lead Code 4 or proprietary equivalent to all abutments.
 - Fixings - Stainless steel or galvanised nails to BS 5534 / manufacturer specs.
 - Straps - 30 x 5 mm galvanised straps at 1.8 m centres (or per structural design).
- RF10.02 | INSTALLATION REQUIREMENTS**
 - Insulation - Install 150 mm mineral wool between joists + 150 mm cross-laid over ceiling joists (total 300 mm). Fit tightly without gaps.
 - Ventilation - Provide **10,000 mm²/m continuous eaves** and **5,000 mm²/m continuous ridge** ventilation. Maintain **minimum 50 mm clear air gap** above insulation.
 - Membrane - Install BS EN 13859-1 compliant breather membrane taut over rafters, lapped per manufacturer.
 - VCL - Install VCL to warm side of insulation. Tape all joints & seal penetrations/perimeters.
 - Tiles - Fix per BS 5534:2014+A2:2020 and Marley schedules for 35° pitch & site exposure.
 - Battens - Install to correct gauge per tile manufacturer; fix securely per BS 5534.
 - Underlay - Install with correct laps & drape; ensure continuity into gutter with eaves support.
 - Flashings - Install correctly dressed flashings to all abutments, penetrations etc.
 - RW Goods - Install rainwater goods as per dedicated specification.
- RF10.03 | STANDARDS & COMPLIANCE**
 - Standards - BS 5534, BS EN 13859-1, BS EN 1995-1-1, BS 5250, BS EN ISO 6946.
 - Building Regs - Meet or exceed Approved Document L1B, F, C, B, A (England & Wales) / Equivalent Regs.
 - Fire Rating - Tiles Euroclass A1; Mineral wool insulation Euroclass A1/A2.
 - Certification - CE/UKCA Marked materials; BBA Certified where available.
 - Condensation - Comply with BS 5250 condensation control requirements.
 - Thermal req. - **Must Achieve - 0.15 W/m²K** - per Part L1B 2021.
 - U-Value - **0.14 W/m²K ✓ Achieved**

CL10 | Stacked Slate Cladding System Specification


- CL10 | PRODUCT DETAILS**
 - Spec Note - This specification is only a standard benchmark, Contractor may specify alternatives
 - Product - STONEPANEL™ INFREGO® - Natural Dark-Toned Slate Panel or similar appearance product
 - Dimensions - 400mm (Length) x 200mm (Height) per panel
 - Thickness - 40mm (±5mm Tolerance)
 - Finish - Natural split-face textured finish
 - Format - "S" shaped panel ends to naturally conceal joints
- CL10 | INSTALLATION REQUIREMENTS**
 - Substrate - Brickwork/Blockwork must be free from dust, debris, loose material
 - Adhesive - Ardex X76+ Flexible Tile Adhesive (C2 TE S1 Classification per BS EN 12004)
 - Application - Minimum 10mm notched bed, 95% coverage, full bedding required - No spot fixing
 - Height Limit - Adhesive-only fixing permitted up to maximum 2.0 metres above ground level
 - IF Over 2.0m - Requires stainless steel anchor fixing integrated into substrate
 - Joints - Vertical movement joints at 6.0m maximum centres or at changes in plane
 - Temperature - External works must proceed only at ambient temperatures >5°C and rising
- CL10 | PERFORMANCE & COMPLIANCE**
 - Fire Rating - A2-s1, d0 (Non-combustible, minimal smoke, no flaming droplets)
 - Standards - BBA Certificate 21/5908 (Durability, Fire, Strength, Moisture Resistance)
 - Building Regs - Compliant with Parts B (Fire), C (Moisture), L (Thermal)
 - Guarantee - 10-year product guarantee when installed per manufacturer guidelines
 - Certification - CE Marked, BBA Certified, Frost-resistant bond, Weather-tested system

CL20 | Composite Cladding System Specification

- CL20.01 | PRODUCT DETAILS**
 - Product - EnviroBuild Hyperion Pioneer Composite Cladding System
 - Finish - "Granite" (Dark Grey) or "Stone" (Medium Grey) **Subject To Client Sample Approval**
 - Dimensions - 120mm Width x 20-21mm Thickness x 3600mm or 2500mm Length
 - Profile - Tongue-and-groove shiplap profile with embossed woodgrain texture
 - Orientation - Boards to be installed horizontally; with appropriate batten arrangement
 - Material - Wood-polymer composite; 60% recycled FSC hardwood fiber, 30-40% recycled HDPE
 - Application - External cladding system applied over existing brickwork outer wall skin
 - Spec Note - This specification is a Quality Benchmark, **Contractor May Specify Alternatives** Any alternative must meet the same performance criteria specified on this document
- CL20.02 | INSTALLATION REQUIREMENTS**
 - Battens - Treated timber (BS EN 335 Use Class 3) or recycled plastic battens
 - Batten Size - Minimum 38mm thick to ensure a suitable ventilated cavity behind cladding
 - Batten Space - Maximum 600mm centres horizontally (for vertical cladding) or vertically (for horizontal)
 - Substrate - Clean, plumb wall surface with breather membrane installed, pack out battens where required
 - Fixings - Stainless steel screws (A2/A4 grade) through board tongue into battens
 - Pre-drilling - Pre-drill board fixing holes 2mm larger than screw diameter to allow thermal movement
 - Air Gap - 20mm minimum ventilation gap at top and bottom of installation
 - Joints - 1-2mm expansion gap at butt joints between board ends; double battens at joints
 - Temperature - Follow manufacturer's temperature guidance for installation
- CL20.03 | PERFORMANCE & COMPLIANCE**
 - Standards - EuroClass D-s1,d0 *Combustible with limited smoke & no flaming droplets*
 - Building Regs - Compliance with Parts B *Fire-Protection*, Part C *Moisture-Control*, Part 7 *Materials*
 - Ventilation - System must be installed as ventilated rainscreen with 38mm min. cavity
 - Guarantee - *15-year* limited residential warranty
 - Certification - FSC® 100% recycled wood certification
- CL20.04 | FIRE PERFORMANCE COMPLIANCE NOTE**
 - Limitation - Specification applies only to masonry substrate construction; alternative substrates require reassessment.
 - Application - Cladding system to be installed over traditional cavity wall external masonry skin.
 - Compliance - Spec provided is acceptable for residential dwellings under 11m height, subject to Building Control approval.
 - Inspection - Building control consultation required for each project's fire requirements
 - Risk Control - Fire barriers to be installed at required locations in accordance with Approved Document B.
 - Liability - Designer specification relates solely to cladding material selection; full compliance remains the responsibility of the principal contractor and Building Control authority.

RP20 | Rear Extension Vaulted Roof Specification

- RP20.01 | MATERIALS & PRODUCT DETAILS**
 - Roof Type - Pitched roof, vaulted internal ceiling, ventilated void above insulation
 - Pitch - 25° Roof Pitch - Hip End
 - Roof Tile - Marley Edgemere interlocking concrete tile, grey finish
 - Rafters - 150mm x 50mm C16 graded timber at 400mm centres
 - Rooflights - 3no. Velux CK02 w550mm x h780mm roof windows
 - Underlay - BS EN 13859-1 LR (Low Resistance) breathable membrane, BBA certified
 - Battens - 25 x 38 mm tanalised treated softwood roofing battens to BS 5534
 - Insulation 1 - 120mm rigid PIR insulation board Min Lambda Val. 0.022 W/mK - fitted between rafters
 - VCL - Vapour Control Layer integral to insulated plasterboard *or* separate 500g (125 micron) polythene sheet.
 - Insulation 2 - 62.5mm Insulated Plasterboard; (50mm PIR Min Lambda Val. 0.022 W/mK + 12.5mm plasterboard) fixed below rafters
 - Ceiling - Integral 12.5 mm plasterboard face of Insulated Plasterboard
 - Finish - 3mm gypsum skim coat plaster finish to ceiling board
 - Flashings - Lead Code 4 (Min) or approved proprietary flashing system to all abutments/penetrations.
 - Fixings - Tile/Batten: Stainless steel or galvanised nails per BS 5534 / manufacturer specs. Insulation/Board: Appropriate length corrosion-resistant screws per board manufacturer instructions.
 - Collar Ties - Timber collars below apex as per structural design/drawings.
- RP20.02 | INSTALLATION REQUIREMENTS**
 - Insulation 1 - Fit 120mm PIR board tightly between rafters, maintain **minimum 30mm clear air gap** above Use insulation support clips if necessary to prevent slumping into air gap
 - Insulation 2 - Fix 62.5mm insulated plasterboard securely to underside of rafters, ensuring tight fit Use correct length and type of fixings as per manufacturer's guidance. Stagger joints
 - Ventilation - Maintain **minimum 30mm clear continuous air gap** between top of PIR (Insulation 1) and underside of roofing underlay, vented continuously from eaves to ridge
 - Membrane - Install BS EN 13859-1 compliant breather membrane taut over rafters, lapped per manufacturer
 - VCL - Install VCL layer to warm side of *all* insulation (i.e., immediately behind plasterboard finish) If using separate sheet VCL: tape all joints & seal penetrations/perimeters before fixing board If using VCL integral to insulated plasterboard: tape board joints with foil tape Seal VCL Layer to Velux BBX VCL collar at rooflights
 - Rooflights - Install per Velux instructions. Use Insulation collar (e.g., BBX) & VCL collar (e.g., BBX)
 - Battens - Ensure correct flashing kit (e.g., EDW) is used. Trimmers doubled up per structural detail
 - Underlay - Install to correct gauge per tile manufacturer; fix securely per BS 5534
 - Flashings - Install with correct laps & drape; ensure continuity into gutter with eaves support
 - RW Goods - Install correctly dressed flashings to all abutments, penetrations etc
 - Install rainwater goods as per dedicated specification
- RP20.03 | STANDARDS & COMPLIANCE**
 - Standards - BS 5534, BS EN 1995-1-1, BS 5250, BS EN 13859-1, BS EN ISO 6946
 - Building Regs - Meet or exceed Approved Document L, F, C, B, A (England & Wales) / Equivalent Regs
 - Fire Rating - Roof Tiles: Euroclass A1. PIR Insulation Core: Typically Euroclass E/F Insulated Plasterboard (Composite): Typically EuroClass B-s1,d0. Verify specific product data
 - Certification - CE/UKCA Marked materials; BBA Certified where available.
 - Condensation - Comply with BS 5250 condensation control requirements
 - Thermal req. - **Must Achieve - 0.15 W/m²K** - per Part L1B 2021.
 - U-Value - **0.15 W/m²K ✓ Achieved**



PE02| East Elevation



Printed Scale Factor | 1mm : 50mm

Scale Valid When Printed At : ISO 216 A1