





EXISTING GROUND FLOOR PLAN



PROPOSED GROUND FLOOR PLAN



FLOOR PLAN & PROPOSAL NOTES

SN01 | Structural design
Structural members shown are indicative. Appoint a structural engineer to inspect the existing building and design foundations, beams, lintels, posts, bearings, connections and lateral restraint. Obtain coordinated calculations and details before structural work; do not derive member sizes from these drawings.

SN02 | Sliding-door opening
Structural engineer to design support over the wide sliding-door opening, including bearings, padstones, supporting piers or posts and foundations. Limit deflection to the door supplier's tolerances. Coordinate head clearance, frame fixings, insulation and weathering before manufacture.

SN03 | Part-cantilevered canopy
Structural engineer to design the canopy, its supported outer edge and cantilevered inner end, including wind uplift, deflection, connections and foundations. Provide a designed loadbearing frame at the slatted screen. Decorative slats are non-loadbearing unless expressly designed otherwise by the engineer.

SN04 | Existing wall alterations
Engineer to assess retained walls, roof loads and stability before enlarging rear openings. Specify permanent support and restraint. Contractor to provide an engineered temporary support and demolition sequence; install supports before removing loadbearing construction. Do not assume existing lintels or foundations are adequate.

SN05 | Foundations and roof framing
Confirm ground conditions, trees, drains and adjacent foundations before foundation design. Do not reuse conservatory foundations without the engineer's verification. Design roof joists and rooflight trimmers for the complete warm-roof build-up, parapets and imposed loads; coordinate openings before fabrication.

EX01 | Existing external walls
Existing house: mixed buff facing brickwork above a blue engineering-brick plinth to DPC level. Retain outside the indicated alterations; make good disturbed areas with matching bricks and mortar. Confirm brick types and DPC level on site.

EX03 | Existing windows and doors
Existing windows and external doors comprise mixed white and brown frames, including uPVC, with varied glazing patterns. Retain except where removal or replacement is indicated. Confirm frame materials, opening arrangements and finishes on site.

EX05 | Conservatory and WC removal
Remove existing conservatory and adjoining flat-roof WC, approximately 3,100 mm projection x 4,350 mm overall width. Isolate services and seal redundant drain connections. Protect retained walls and roof; make good exposed junctions. Confirm demolition extent and any retained foundations on site.

WF01 | Monocouche render
Proprietary monocouche render to indicated walls above DPC; colour: Chalk or Silver Pearl, subject to final manufacturer and sample approval. Apply the complete compatible system to the specified substrate, with beads and movement joints. Terminate above DPC; do not bridge the damp-proof course.

PD01 | Rear extension projection
Single-storey rear extension with an enclosed projection of 3,150 mm from the rear wall of the house. This dimension describes the enclosed accommodation; the external canopy is shown separately.

PD02 | Extension width
Extension width: 9,230 mm. The enclosed extension remains within the existing side-wall lines of the house, as shown on the plans.

RF01 | Warm flat roof
Warm-roof construction behind a parapet, with insulation above the structural deck and a continuous vapour control layer below the insulation. Coordinate thermal performance, condensation control, waterproofing and abutments in the construction details. Form falls to outlets within the stated height envelope.

RF03 | Flat rooflights
Three flat rooflights, nominally 1,500 x 1,000 mm each: two over the dining/occasional seating area and one over the bedroom. Confirm whether dimensions refer to the opening or overall unit before ordering. Provide insulated upstands at least 150 mm above the adjacent finished roof surface.

RF04 | Rooflight pitch and height
Install rooflights at the manufacturer's required pitch; 5 degrees is indicative. Keep frames and glazing below the coping. The indicated roof-to-coping allowance is 200 mm; coordinate the minimum 150 mm upstand, frame depth and pitch within this envelope. Revise the roof detail if necessary; do not reduce the minimum upstand.

OP01 | East-facing sliding doors
Large glazed sliding doors to the east, garden-facing elevation. Frame material, colour, panel arrangement and opening direction to be confirmed. Coordinate structural opening and deflection tolerances with the supplier. Provide safety glazing, weather seals and a drained threshold; confirm thermal performance and ventilation in the construction specification.

OP02 | East-facing bedroom window
New uPVC window to the bedroom on the east, garden-facing elevation. Colour and opening arrangement to be agreed. Coordinate glazing, ventilation and any required escape opening with the Building Regulations design; confirm clear opening dimensions and sill height before ordering.

PR02 | Vertical metal screen
Open screen of vertical powder-coated metal slats to one side of the canopy; metal type, section, spacing and colour to be agreed. Fix to a corrosion-protected supporting frame. Retain open gaps between slats. Canopy loads to be carried by the engineer-designed structure, not decorative infill.

GN01 | Drawing scope
Drawings describe the proposed development for planning assessment. They are not construction drawings or a complete Building Regulations specification. Obtain coordinated construction details, structural calculations and Building Control approval before relevant work starts. Refer discrepancies to Noble Architecture before proceeding.

GN02 | Survey and dimensions
Prepared from client-supplied photographs and measurements; Noble Architecture has not undertaken a measured site survey. Verify dimensions, levels, boundaries and existing construction on site before design, ordering or setting out. Use stated dimensions; do not scale for construction. Report discrepancies before work proceeds.

