




Existing | Street Scene Elevation



NB01 | Boundary Wall Design & Aesthetic

The existing front boundary wall and tall, unmanaged wild hedgerow are to be removed and replaced by a new, high-quality brick boundary wall. This will incorporate painted horizontal slatted timber or composite infill panels between the piers, with a smaller, managed ornamental hedgerow planted behind. To ensure absolute aesthetic cohesion, the decision has been made to completely knock down and rebuild the wall rather than extending the existing brickwork. This guarantees a uniform, perfect brick match from base to Capping, which would be impossible to achieve if extending on top of the aged existing piers.

NB02 | Pier Proportions & Access

The new piers will occupy the exact same footprint positions as the original piers. Therefore, there is no change to the width of the existing driveway opening; the piers are being extended in height only. We have consciously chosen to maintain the existing 335 x 335mm pier footprint rather than increasing them to a bulkier 450mm. This ensures the taller piers do not look overly thick, out of balance, or detrimentally alter the character of the street scene, particularly as the low-level wall sections remain relatively low.

NB03 | Coping & Weathering

There is no real raise in the main low-level wall section height. The spans between the pillars will be capped with a traditional brick-on-edge and tile creasing detail. This provides a highly robust weathering detail, significantly reduces the risk of frost spalling, and visually ties the boundary treatment into the established aesthetic of the neighbour's wall.


NB04 | Street Scene Datum & Levels Note

All vertical dimensions and heights shown on these Street Scene Elevations (both Existing and Proposed) are measured from an arbitrary Local Datum point. This datum is indicated by the red target symbol located at the existing ground level, centrally positioned between the two principal vehicular driveway piers. This arbitrary datum is unique to this drawing sheet only. Plans and elevations on other sheets within this application pack (such as the Proposed Garage Elevations) utilize a separate local datum tied to the Finished Floor Level (FFL) of the newly constructed garage. Planning Officers and Contractors must bear this in mind and should not directly cross-reference vertical heights between this sheet and the garage elevations without accounting for the site's existing topographical ground level variations.


ST01 | Pier Structural Reinforcement

Note to Contractor: As the 335 x 335mm piers are being extended in height and will be subject to lateral wind loading from the new horizontal slatted infill panels, they cannot be constructed as standard unreinforced masonry. The piers must be constructed with a hollow core and be internally reinforced (e.g., utilising a central H16 high-yield steel rebar or M16 threaded steel rod, cast deeply into the concrete foundation footing and backfilled with concrete, or a bolted galvanized steel wind post).

Disclaimer: This drawing has been produced for Planning Application purposes only and does not constitute a structural specification. Noble Architecture accepts no liability for the structural integrity, stability, or performance of the boundary wall or piers. The final specification of internal steel reinforcement, wind-load calculations, foundation depths, and Building Regulations compliance remain strictly the sole responsibility of the appointed principal contractor and/or a qualified Structural Engineer prior to the commencement of works.



Proposed | Street Scene Elevation



NB05 | Vehicular Access & Visibility Splays

The existing driveway opening width (4100mm) and footprint are retained completely unaltered. The proposed boundary wall and extended piers have been explicitly designed to ensure that the existing pedestrian and vehicular visibility splays remain entirely unaffected by the proposal.

General Note | Planning Purpose Only

This document has been prepared explicitly for the purpose of a Planning Application. To ensure clarity for the Planning Officers assessment, the document pack is intentionally lightweight and omits detailed technical specifications, including structural arrangements, wall compositions, and floor / roof build-ups. Consequently, these documents are strictly not fit for construction purposes or Building Regulations approval. Comprehensive technical design and structural engineering plans must be commissioned and approved at a subsequent stage prior to the commencement of any works.